

Case Studies

# Donnybrook Sewer Manhole Yarra Valley Water

Vortex chamber drop pipe,  
designed in house and supplied as  
complete unit. Converted from  
concrete to GRP  
Location: Melbourne, VIC



DN3000 GRP  
Manhole, 15m  
Deep.

2-day installation  
compared to 8  
weeks cast in-situ  
concrete option.

